Items of work	Per	Rate	Quantity	Cost
Sluice R. L. 45·00.		Rs. a. p.		Rs.
Earthwork—				
1. Excavating earth	C.yd.		55	
2. Refilling with watering and tamping ...	,,		60	
3. Concrete in surki mortar	C.ft.		177	
4. Burnt brick in surki mortar	,,		421	
5. Burnt stone slabs 6" thick	S.ft.		146	
6. Boring hole in slabs	Lump	sum	..	
7. Plasting with surki mortar	Sqr.		3·68	
8. Cast iron pipe 5" diameter	R.ft.		27	
9. Plug and rod with locking arrangements ...	Lump	sum	...	
Total Sluice ...	...	... .	...	...
Weirs at R. L. 50·00.				
Left weir—				
1. Earthwork clearing site	C.yd.		462	
2. New stone work	,,		129	
3. Toe slabs	S.ft.		144	
4. Pin slabs 12'×1'	Each		14	
5. Concrete in surki granting	Lump	sum	...	
Total Left Weir ...	...	... ...	...	...
Right Weir—				
1. Clearing site	Lump	sum	...	
2. Excavating foundation bard chettu soil ...	C.yd.		45	
3. Chistling soft rock	Lump	sum	..	
4. Earthwork to flank	C.yd.		432	
5. New stone work	,,		91	
6. Burnt stone slabs	S.ft.		72	
7. Pin slabs	Each		6	
8. Surki concrete granting	Lump	sum	...	
Total Right Weire ...	...	.. ..	...	..
Total of bund, sluice and weir contingencies at 5 per cent.	...	... ...	...	...
Grand Total ...	...	... ...	...	...

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Notice dated 31st January 1929.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Tumkur Division, up to 18th February 1929, for constructing a District Board Office Building at Tumkur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of August 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

3A. No percentage rates or so much less or more than the estimate will be accepted.

4. Each tender must be accompanied by a deposit of rupees 1,000 (one thousand only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a District Board Office Building at Tumkur" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for constructing a District Board Office at Tumkur.

No.	Items of work	Per	Quantity	Rate	
				In figures	In words
				Rs.	Rs.
1	Earthwork excavation and filling in basement including watering and tamping.	C.yd.	346		
2	Filling foundation with concrete stone jelly and chunam.	C.ft.	1726		
3	Burnt stone in mud foundation with bond stones 6 ft. apart in every layer.	„	5904		
3A	Burnt stone in mud hammer dressed basement with bond stones 6 ft. apart in every layer.	„	2750		
4	Burnt brick in lime mortar ...	„	7419		
5	Burnt stone slabs 6″ thick dressed ...	S.ft.	1462		
6	Burnt stone slabs 6″ to 9″ thick nicely dressed and cutting grooves for the seat of steel girders.	S.ft.	141		
7	Wire cut brick round pillars 8½ ft. in height including base and capital with ornamentation, etc., complete including cornice.	No.	26		
8	Chunam plastering ½″ thick	Sqr.	116·43		
9	Rolled steel girders of approved firmes including hoisting and cross-joists for semi-circular portion, painting with whitelead, etc., complete.	Cwts.	128·63		
10	Whitewashing two coats	Sqrs.	116·43		
11	Teakwood work wrought and put up with wood oiling.	C.ft.	467·74		
12	Teakwood doors 1½″ thick paneled shutters with glass ventilator including cross-bars at top and iron clamps, etc., complete as per Marryat Specification.	„	599½		

No.	Items of work	Per	Quantity	Rate	
				In figures	In words
				Rs. a. p.	Rs.
13	Teakwood windows 1½″ thick shutters with 3¼″ iron bars 5″ a part with double shutters one side glazed and other side paneled with glass ventilators fixed at top, complete.	S.ft.	390		
14	Teakwood ventilators with glazed shutters, iron bars with hooks and ropes, etc., complete.	,,	138		
15	Roofing the pucca terrace 9″ thick including surki concrete 3 course of flat tiles, chunam plastering on both sides.	Sqrs.	44·58		
16	Cornice 12″ including masonry and plastering	R.ft.	313		
17	Do 9″ do do ...	,,	293		
18	Parapet wall 2′ in height with masonry plastering cornice etc., complete.	,,	282		
19	Flooring with 2″ to 3″ granite slabs two line dressed over 3″ concrete and cement pointing including, etc.	Sqrs.	14·86		
20	Flooring with Mangalore tiles over 3″ concrete and cement pointing.	,,	20·02		
21	Chunam pointing	,,	8·75		
22	Extra earthwork filling in basement with carting ¼ mile lead	C.yd.	72		
23	Varnishing two coats	Sqrs.	21·77		
24	Silicate chocolate painting... ...	,,	3·12		
25	Masonry (brick in chunam) ornamental parapet as per elevation including curveing letters and figures and painting, complete.	Lump	sum		
26	Fixing a flag post with flag pullies guys, etc., complete.	,,	,,		
27	Clearing site and levelling ground with filling gravel including unforeseen works.	,,	,,		
28	Giving water connection to the building by galvanized pipes, bends and constructing taps in the compound of the building.	,,	,,		

V. V. PATANKAR,
Executive Engineer.

MYSORE SPECIAL DIVISION.

Notice dated 28th January 1929.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Special Division, Mysore, up to 27th February 1929, till 12 noon for constructing a Sandal Koti Building at Mysore. An abstract of approximate quantities given below. These quantities are not guaranteed. The work should be completed by the end of Septmber 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M. on the working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty (Rs. 250) in cash or Government Promissory Notes, State Loan Bonds at market rates or in Savings Bank Pass Book of the tenderer having that amount at his credit on that date as earnest money and be superscribed "Tender for constructing a Sandal Koti Building at Mysore" in default of which tenders will be rejected.